

RV Setup Checklist

⌚ Remember to take your time!

FOUR CHECKS BEFORE YOU CHOCK

- You can reach the water & electrical connections
- Slides have enough room to clear obstacles
- Use a Spotter when backing into a site
- RV is level left to right (use leveling blocks if needed)

RV EXTERIOR

- Chock your tires
- Disconnect trailer from tow vehicle
- Level the trailer from front to back.
- Deploy stabilizers
- Connect the surge protector independently to the panel to ensure the proper lights, turn the panel off and connect the power cord to your RV. Then turn the panel back on.
- Connect to water (make sure water pressure regulator is connected)
- Connect sewer hose (keep valves closed until dumping needed)
- Turn propane valves on when needed.

RV INTERIOR

- Fridge/Freezer On and AUTO selected
- Check inside and outside for obstacles before extending slide
- Deploy RV Slide (use a spotter)
- Turn on A/C or Heat
- Check Water Level (N/A for city hookup)
- Water Pump On (N/A for city hookup)
- Water Heater On (Use electric)

FINAL CHECK

- Review Renter's Assistance Guide
- HAVE FUN!

⚠ NOTE: Make sure water is in the fresh tank and fresh tank drain is closed before turning water pump on.

⚠ NOTE: Run the hot water at a faucet prior to turning the hot water heater on for 5-10 seconds.

Tips, Troubleshooting and How-to

